

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-009-01453-00-00  
Spot: SW Sec/Twnshp/Rge: 31-19S-13W  
1650 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: THIES Well #: 1  
County: BARTON Total Vertical Depth: 3554 feet

Operator License No.: 34434  
Op Name: EDISON OPERATING COMPANY LLC  
Address: 8100 E. 22ND ST. N., BLDG 1900  
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3554		150 SX
SURF	8.625	768		400 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/28/2014 1:00 PM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: ROCH MILLER Company: EDISON OPERATING Phone: (620) 786-5161

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls and 15 sx gel.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/28/2014 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1400' and 760'. Ran tubing to 3296' and pumped 15 sx gel followed by 50 sx cement w/100 # hulls. Pulled tubing to 1400' and pumped 70 sx cement w/100 # hulls. Pulled tubing to 750' and pumped 40 sx cement w/100 # hulls. Pulled tubing to 400'. Circulated cement to surface on casing w/165 sx cement. Pulled tubing. Tied to casing and circulated cement to surface and backside w/110 sx cement.

GPS: 38.34177 -098.80314

Perfs:

Top	Bot	Thru	Comments
3482	3490		

Received  
KANSAS CORPORATION COMMISSION

Remarks: ALLIED CEMENTING

Plugged through: TBG

NOV 03 2014

CONSERVATION DIVISION  
WICHITA, KS

District: 04

Signed Bruce Rodie  
11/5/14 CKM (TECHNICIAN)

CM

NOV 30 2014