

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-19042-00-00
Spot: SWNENW Sec/Twnshp/Rge: 16-19S-12W
4290 feet from S Section Line, 3630 feet from E Section Line
Lease Name: SCHWERTFEGER Well #: 1
County: BARTON Total Vertical Depth: 3451 feet

Operator License No.: 34434
Op Name: EDISON OPERATING COMPANY LLC
Address: 8100 E. 22ND ST. N., BLDG 1900
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3310		75 SX
SURF	8.625	213		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/27/2014 9:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: ROCH MILLER Company: EDISON OPERATING Phone: (620) 786-5161

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/27/2014 1:30 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1400', 690' and 200'. Ran tubing to 3196' and pumped 13 sx gel followed by 50 sx cement w/100 # hulls. Pulled tubing to 1400' and pumped 70 sx cement w/100 # hulls. Pulled tubing to 700' and pumped 40 sx cement w/100 # hulls. Pulled tubing to 350'. Circulated cement to surface on casing w/50 sx cement. Pulled tubing. Tied to backside and pumped 50 sx cement.

GPS: 38.40290 -098.6537

Perfs:

Top	Bot	Thru	Comments
3190	3193		

Received
KANSAS CORPORATION COMMISSION

NOV-03-2014

Remarks: ALLIED

Plugged through: DP ^{TBG}

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed Bruce Rodie
11/5/14 CKM (TECHNICIAN) CM

OCT 28 2014