

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-175-20582-00-00
Spot: SWNESWNW Sec/Twnshp/Rge: 13-34S-31W
1926 feet from N Section Line, 952 feet from W Section Line
Lease Name: N. KEATING Well #: 1-13
County: SEWARD Total Vertical Depth: 6188 feet

Operator License No.: 33725
Op Name: FOUNDATION ENERGY MANAGEMEN
Address: 16000 NORTH DALLAS PKWY, STE 875
DALLAS, TX 75248

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2015		WITH 2 SX CMT
CIBP		5390		WITH 2 SX CMT
CIBP		5930		
PROD	4.5	6188	0	WITH 350 SX CMT
SURF	8.625	1484		WITH 800 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/16/2014 11:00 AM
Plug Co. License No.: 34199 Plug Co. Name: RAWHIDE WELL SERVICE, LLC
Proposal Rcvd. from: HOMER MADDEN Company: FOUNDATION ENERGY Phone: (580) 559-1301

Proposed Plugging Method: SET CIBP @ 5390' WITH 2SX CMT. SET CIBP @ 2015' WITH 2 SX CMT. TEST CASING TO 500 PSI. PERFORATE AT 1520' WITH 15 SX GEL & 50 SX CMT. PERFORATE AT 550' & CIRCULATE CMT TO 0'.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/16/2014 6:30 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 5390' WITH 2 SX CMT. SET CIBP @ 2015' WITH 2 SX CMT TO COVER CASING LEAKS 2066-2097'. TEST CASING TO 500 PSI. 1ST PLUG PERFORATE AT 1520' WITH 200 SX CMT. 2ND PLUG PERFORATE AT 550' WITH 125 SX CMT TO 0'.

Perfs:

Top	Bot	Thru	Comments
5928	6049		
5440	5448		

Received
KANSAS CORPORATION COMMISSION
NOV 03 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED COMMON CEMENT BY PARTNERS OILFIELD.

Plugged through: TBG

District: 01

RECEIVED
OCT 30 2014
KCC DODGE CITY

Signed [Signature]
11/5/14 CKM (TECHNICIAN)