

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-24181-00-00
Spot: SENWNWNW Sec/Twnshp/Rge: 12-9S-18W
600 feet from N Section Line, 500 feet from W Section Line
Lease Name: SIMPSON TRUST Well #: 1
County: ROOKS Total Vertical Depth: 3590 feet

Operator License No.: 5552
Op Name: GORE OIL COMPANY
Address: 202 S ST FRANCIS PO BOX 2757
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3583		140 SX
SURF	8.625	261		170 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/20/2014 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: LENNY DINKEL Company: GORE OIL CO. Phone: (785) 259-1928

Proposed Plugging Method: Ordered 440 sx 60/40 pozmix 4% gel cement w/600 # hulls.
Production perforations: 3183' - 3507'

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/20/2014 10:30 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Hooked to 5 1/2" casing and pumped 320 sx cement w/600 # hulls. Shut in pressure 500 psi.
Hooked to 8 5/8" x 5 1/2" annulus and pumped 120 sx cement. Shut in pressure 100 psi.
GPS: 39.29072N -099.28683W

Perfs:

Top	Bot	Thru	Comments
3497	3507		
3276	3280		
3267	3269		
3233	3236		
3183	3185		

Received
KANSAS CORPORATION COMMISSION

Remarks: ALLIED TICKET # 55349

NOV 03 2014

Plugged through: CSG

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed

Pat Bedore
11/5/14 CKM (TECHNICIAN)

CM

OCT 27 2014