

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-097-21707-00-00
Spot: SWNWSENE Sec/Twnshp/Rge: 28-27S-18W
1656 feet from N Section Line, 1117 feet from E Section Line
Lease Name: JUNGEMANN Well #: 1-28
County: KIOWA Total Vertical Depth: 4866 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4342		WITH 2 SX CMT
CIBP		4700		
CIBP		4780		
PROD 5.5		4864	2011	WITH 200 SX CMT
SURF 8.625		562		WITH 350 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/28/2014 11:30 AM

Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP

Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: SET CIBP @ 4340' WITH 2 SX CMT. PLUG AT 1200' WITH 12 SX GEL & 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN
Date/Time Plugging Completed: 10/28/2014 3:30 PM

Witness Type: PARTIAL
KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4342' WITH 2 SX CMT. 1ST PLUG AT 1211' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 611' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4788	4802		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY SERVICES.

Plugged through: CSG

Received
KANSAS CORPORATION COMMISSION
NOV 03 2014
CONSERVATION DIVISION
WICHITA, KS

District: 01

RECEIVED
OCT 29 2014
KCC DODGE CITY

Signed Eric MacLaren
11/5/14 CEM (TECHNICIAN)