

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-151-22210-00-00
Spot: NESWSESE Sec/Twnshp/Rge: 23-26S-11W
526 feet from S Section Line, 860 feet from E Section Line
Lease Name: MEIREIS Well #: 1-23
County: PRATT Total Vertical Depth: 4370 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4190		WITH 2 SX CMT
CIBP		4250		
PROD	5.5	4370	2221	WITH 200 SX CMT
SURF	8.625	454		WITH 350 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/24/2014 10:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: CIBP @ 4190' WITH 2 SX CMT. PLUG AT 700' WITH 10 SX GEL & 50 SX CMT. PLUG AT 500' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN
Date/Time Plugging Completed: 10/24/2014 12:30 PM

Witness Type: COMPLETE (100%)
KCC Agent: ROBERT DICKERSON

Actual Plugging Report:

SET CIBP @ 4190' WITH 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 700' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 500' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4290	4294		SPF
4240	4244		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID & CEMENT.

Plugged through: CSG

Received
KANSAS CORPORATION COMMISSION

NOV 03 2014

CONSERVATION DIVISION
WICHITA, KS

District: 01

Signed

Robert Dickerson

11/5/14 CLKM

(TECHNICIAN)

RECEIVED

OCT 29 2014

KCC DODGE CITY

Form CP-2/3