

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-151-22215-00-00
Spot: SENE Sec/Twnshp/Rge: 27-26S-11W
4174 feet from S Section Line, 336 feet from E Section Line
Lease Name: MOORE Well #: 1-27
County: PRATT Total Vertical Depth: 4380 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4270		WITH 2 SX CMT
PROD	4.5	4379	1806	WITH 175 SX CMT
SURF	8.625	463		WITH 150 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 10/16/2014 2:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: SET CIBP @ 4270' WITH 2 SX CMT. PLUG AT 710' WITH 10 SX GEL & 40 SX CMT. PLUG AT 500' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/16/2014 4:35 PM KCC Agent: ROBERT DICKERSON

Actual Plugging Report:

SET CIBP @ 4270' WITH 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 710' WITH 10 SX GEL & 40 SX CMT. 2ND PLUG AT 500' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4293	4295		

Received
KANSAS CORPORATION COMMISSION

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID & CMT.

NOV 03 2014

Plugged through: CSG

CONSERVATION DIVISION
WICHITA, KS

District: 01

Signed Robert Dickerson
11/5/14 CKM (TECHNICIAN)

RECEIVED
OCT 29 2014
KCC DODGE CITY