

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-175-21570-00-00
Spot: NWNE Sec/Twnshp/Rge: 31-34S-32W
660 feet from N Section Line, 1980 feet from E Section Line
Lease Name: BLACKMER A Well #: 2
County: SEWARD Total Vertical Depth: 6650 feet

Operator License No.: 32446
Op Name: MERIT ENERGY COMPANY, LLC
Address: 13727 NOEL RD STE 1200
DALLAS, TX 75240

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		6284		WITH 2 SX CMT
CIBP		6397		
PROD	5.5	6470	2418	WITH 160 SX CMT
SURF	8.625	1604		WITH 470 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/29/2014 10:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: JOEL Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: SET CIBP @ 6284' WITH 2 SX CMT. CIRCULATE HOLE WITH MUD. PLUG AT 1634' WITH 50 SX CMT. PLUG AT 500' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: NONE
Date/Time Plugging Completed: 10/29/2014 3:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

CIBP @ 6284' WITH 2 SX CMT. 1ST PLUG AT 1660' WITH 80 SX CMT. 2ND PLUG AT 500' WITH 60 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
6334	6352		

Received
KANSAS CORPORATION COMMISSION
NOV 03 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: **CONPLIANCE ISSUE: DENIED TA SI 10 YRS** USED COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

RECEIVED
OCT 30 2014

Signed [Signature]
(TECHNICIAN)

11/5/14 ckm

KCC DODGE CITY