

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-24214-00-01
Spot: S2S2 Sec/Twnshp/Rge: 5-17S-13W
660 feet from S Section Line, 2640 feet from E Section Line
Lease Name: HOFFMAN OWWO Well #: 1
County: BARTON Total Vertical Depth: 3393 feet

Operator License No.: 30458
Op Name: RJM COMPANY
Address: PO BOX 256
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3382	1729	125 SX
SURF	8.625	210		210 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/29/2014 10:00 AM
Plug Co. License No.: 32098 Plug Co. Name: CLASSIC WELL SERVICE, INC.
Proposal Rcvd. from: CHRIS HOFFMAN Company: RJM CO Phone: (620) 587-3600

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls and 15 sx gel.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/29/2014 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1450', 860' and 350'. Ran tubing to 3300' and pumped 15 sx gel followed by 50 sx cement w/100 # hulls. Pulled tubing to 1450' and pumped 70 sx cement w/100 # hulls. Pulled tubing to 850' and pumped 50 sx cement w/100 # hulls. Pulled tubing to 350'. Circulated cement to surface on casing with 60 sx cement. Pulled tubing. Tied to casing. Circulated cement to surface on backside w/90 sx cement

GPS: 38.59602 -098.78445

Perfs:

Top	Bot	Thru	Comments
3382	3393		

Received
KANSAS CORPORATION COMMISSION

Remarks: COPELAND ACID AND CEMENTING TICKET # 36395

Plugged through: TBG

NOV 03 2014

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed

Bruce Rodie
(TECHNICIAN)

11/5/14 ckm

CM

OCT 30 2014