

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-145-21631-00-00  
Spot: NENWSE Sec/Twnshp/Rge: 13-21S-16W  
2297 feet from S Section Line, 1641 feet from E Section Line  
Lease Name: FLESKE Well #: 1-13  
County: PAWNEE Total Vertical Depth: 3927 feet

Operator License No.: 31725  
Op Name: SHELBY RESOURCES LLC  
Address: 445 UNION BOULEVARD SUITE 208  
LAKWOOD, CO 80228

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3770		WITH 2 SX CMT
PROD	5.5	3891	2078	WITH 200 SX CMT
SURF	8.625	979		WITH 450 SX CMT

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/23/2014 2:00 PM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: JIM Company: D S & W WELL SERVICING, INC. Phone: (620) 793-5838

Proposed Plugging Method: CIBP @ 3770' WITH 2 SX CMT. PLUG AT 800' WITH 10 SX GEL & 50 SX CMT. PLUG AT 450' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/23/2014 4:00 PM KCC Agent: ROBERT DICKERSON

Actual Plugging Report:

SET CIBP @ 3770' WITH 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 800' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 450' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3849	3852		
3835	3837		
3833	3837		
3825	3827		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OILWELL CEMENTING.

Received  
KANSAS CORPORATION COMMISSION

Plugged through: CSG

NOV 03 2014

CONSERVATION DIVISION  
WICHITA KS

District: 01

Signed Robert Dickerson  
11/5/14 ckm (TECHNICIAN)

RECEIVED  
OCT 29 2014  
KCC DODGE CITY

Form CP-2/3