

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-03801-00-00
Spot: SWSESENW Sec/Twnshp/Rge: 23-26S-18E
2450 feet from N Section Line, 2100 feet from W Section Line
Lease Name: HARNER Well #: L-30B
County: ALLEN Total Vertical Depth: 840 feet

Operator License No.: 5491
Op Name: W & W PRODUCTION COMPANY, GEN
Address: 1150 HWY 39
CHANUTE, KS 66720

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2	0		0 SX
PROD	2	850		
SURF	8	0		0 SX
SURF	8	20		

Well Type: OIL UIC Docket No: Date/Time to Plug: 10/03/2014 12:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: MIKE WIMSETT Company: Phone: (620) 431-4137

Proposed Plugging Method: Run 1" inside 2" to TD 840' & circulate cement to 0'. Run 1" outside of 2" to TD 840' & circulate cement to 0". No Pit.

Plugging Proposal Received By: WitnessType: NONE
Date/Time Plugging Completed: 10/03/2014 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Perfs:

Ran 1" pipe inside the 2" casing to TD. Ran 1" pipe outside the 2" casing inside the 8" casing to TD. Pumped and circulated cement through the 1" pipe inside the 2" casing from TD to surface. Pumped and circulated cement through the 1" pipe outside the 2" casing and inside the 8" casing from TD to surface. Pulled both strings of 1" pipe and topped the well off with cement. A total of 140 sacks of portland cement was reported used to plug this well.

RECEIVED

OCT 13 2014

KCC Chanute Dist. #3

RD

Received
KANSAS CORPORATION COMMISSION

OCT 16 2014

CONSERVATION DIVISION
WICHITA, KS

Remarks:

Plugged through: TBG

District: 03

Signed

[Signature]
10/17/14 CEM
(TECHNICIAN)