

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-22660-00-00  
Spot: W2NWNWNW Sec/Twnshp/Rge: 15-13S-16W  
4967 feet from S Section Line, 5090 feet from E Section Line  
Lease Name: REIDEL (RIEDEL) Well #: 1  
County: ELLIS Total Vertical Depth: 3500 feet

Operator License No.: 101  
Op Name: KCC FEE FUND PLUG  
Address: 130 S MARKET  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3491		200 sx
SURF	8.625	197		125 sx

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/31/2014 8:30 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Revd. from: KCC Company: RICHARD MCINTYRE Phone: (620) 727-3409

Proposed Plugging Method: Ordered 220 sx 60/40 pozmix 4% gel cement w/600 # hulls.  
Control # 2014001-001  
Dig safe # KS14019909

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/31/2014 12:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

Drilled on iron and junk in the hole and got down to 1175'. Braden head was dug out and found to be full of cement.  
01/31/2014- Perforated at 575' and 1125'. Ran tubing to 1145' and pumped 165 sx cement w/100 # hulls. Cement circulated out the back side. POOH. Filled casing with 20 sx cement. Hooked on to casing and pumped cement until achieving 350 psi. Shut in pressure 300 psi.

GPS: 38.92858 -098.09432

KCC WICHITA  
JUN 30 2014  
RECEIVED

Remarks: QUALITY WELL SERVICE TICKET # 7835 CONTROL # 2014001-001 KCC REIDEL FEE FUND PROJECT

Plugged through: TBG

District: 04

Signed

Ray A. Dinkel

(TECHNICIAN)

cm

JUN 25 2014

~~JUN 24 2014~~