

6 070450

PLUGGED 230 R

API NUMBER 15-051-20265-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C-5 1/2 SW 5 SEC. 28, T 15 S, R 20 E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5146

_____ feet from S section line

_____ feet from E section line

Operator: Rains and Williamson Oil Co
Name & Address: 435 Page Ct. 220 Douglas
Wichita, Kans 67202
Wilson Rains, Pres.

Lease Name North Well # 8

County Ellis 129.22

Well Total Depth 3976 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8" feet 224

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor B.J. Titan License Number _____

Address Alays, Kans. 67601

Company to plug at: Hour: 10:00 AM Day: 14th Month: Feb. Year: 19 86

Plugging proposal received from Serald Phaschek

(company name) Rains & Williamson Oil Co (phone) 625-7871

were: 8 5/8" - 224^{SK} / 160^{SK} cmt, 5 1/2" cas set @ 3974^{SK} / 150^{SK} cmt

5 1/2" cas. squeezed @ 1066^{SK} / 94^{SK} / 185^{SK} cmt, open hole 2 ft. No Pipe Recovery

Elv. 2268' thru 1490', Perforated @ 1500^{SK} (Amhydrite) 2 Toes

Ordered 300^{SK} / 40^{SK} Pozmix 6% Gel, 22^{SK} Gel, 6^{SK} Shells, 5 1/2" Plug

Load Annulus and pressure with Cement, Load & Pressure 5 1/2" cas

with Pump truck Plugging Proposal Received by [Signature] (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:20 PM Day: 14th Month: Feb Year: 19 86

ACTUAL PLUGGING REPORT Ordered 300^{SK} / 40^{SK} Pozmix 6% Gel, 22^{SK} Gel, 5^{SK} Shells & Plug

Pumped in Annulus 50^{SK} cmt 1/1^{SK} Shells, Max Pressure 600^{PSIG}

shut in at 300^{PSIG}

Pumped in 5 1/2" cas - 2^{SK} Shells, 50^{SK} cmt 1/1^{SK} Shells, 1500^{PSIG}.

Pumped in another 100^{SK} cmt 1800^{PSIG}, Released Plug

and 10^{SK} cmt. Max Pressure 2000^{PSIG}, shut in @ 1800^{PSIG}

Remarks: Cemented By B.J. Titan, Perforated By Mercury Wire Line.

(if additional description is necessary, use BACK of this form)

INVOICED

DATE FEB 26 1986

INV. NO. 12688

RECEIVED STATE CORPORATION COMMISSION

Signed [Signature] (TECHNICIAN)

FEB 21 1986

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
Rev. 01-84