

4-060976

E-18,106

K

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

9-27

API Number: 15-009-20,288 0000

SE NW NE /4 SEC. 18, 20 S, 12 W  
4290 feet from S section line  
1650 feet from E section line

Operator license# 9339

Lease Batchman Well # 1-V

Operator: K & K Oil

County: Barton 113.52

Address: P.O. Box 176  
Chase, Kansas 67524

Well total depth 3493 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 248 feet

Aband. oil well, Gas well, Input well X, SWD, D & A

Plugging contractor: Mike's Testing & Salvage, Inc. License# 31529

Address: Box 209 - Chase, Kansas 67524

Company to plug at: Hour: 11:00 A.M. Day: 27 Month: September Year: 1996

Plugging proposal received from: Darrell Kelso

Company: K & K Oil Phone: 316-938-2943

Were: Order 210 sxs 60/40 posmix - 10% gel - hulls.  
Plug while pulling casing.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [ X ], Part [ ], None [ ]

Completed: Hour: 1:00 P.M., Day: 27, Month: September, Year: 1996

Actual plugging report: 8 5/8" to 248' w/225 sxs. 5 1/2" to 3491' cwc with 150 sxs. Sanded to 3150' and spotted 5 sxs cement with dump bailer. Casing parted two joints down with no stretch indicating well had been squeezed. Shot holes at 615' and 1480'. Tied onto surface pipe and pumped 210 sxs cement with 700# hulls. Max. P.S.I. 450#. S.I.P. 100#.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO  
Bottom plug(in place): YES X, CALC NO, NO Dakota plug: YES X, NO  
Plugged through TUBING SE-11 V, CASING X. Elevation: 1848 GL

INVOICED I did [ X ] / did not [ ]

RECEIVED KANSAS CORP. 10-09-96

[Signature] (agent) Form CP-2/3

DATE 10-10-96

INV. NO. 46677