

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

2-8
API NUMBER 15- 009 - 22625 - 0000
NE, SEC. 18, T. 20 S, R. 12 W/E
3630 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9339

Lease Name Batchman Well # 1

Operator: K and K Oil

County Barton 111.61

Name & Address Box 176

Well Total Depth 3434 feet

Chase, Ks. 67524

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 331

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling Inc. License Number 6050

Address Box 347 Chase, Ks. 67524

Company to plug at: Hour: 10:00AM Day: 8 Month: Feb Year: 19 89

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling Inc. (phone) 316-938-2457

were: Order 200 sks 60/40 Poz 8% Gel 3% Cal Cl 5 sks Hulls.

RECEIVED
STATE CORPORATION COMMISSION

MAR 21 1989

03-21-89

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Gilbert G. Scheck
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:00AM Day: 8 Month: Feb Year: 19 89

ACTUAL PLUGGING REPORT 8 5/8" set at 331' w/285 sks. 4 1/2" set at 3428' w/175 sks.

Top perf at 3311'. Plugged bottom w/sand and 4 sks cement to 3251'. Shot pipe one time and recovered 2685'. Pumped in 8 5/8" 25 sks cement followed w/5 sks Hulls in 175 sks cement w/1300 psi. Ran wireline to 1000'.

Remarks: By Allied.
(If additional description is necessary, use BACK of this form.)

~~Observe this plugging.~~

Signed Gilbert G. Scheck
(TECHNICIAN)

DATE 3-21-89

INV. NO. 24170