

5-18

4-060397

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-009-22,744 0000

NW NE NE /4 SEC. 18, 20 S, 12 W
4950 feet from S section line
1060 feet from E section line

Operator license# 4707 Lease Sessler well # 2

Operator: Carl Boxberger Oil, Inc. County Barton

Address: P.O. Box 1604 Well total depth 3625 feet
Great Bend, Kansas 67530 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 320 feet

117.81

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Kelso Casing Pulling, Inc. License# 6050

Address: P.O. Box 347 - Chase, Kansas 67524

Company to plug at: Hour: A.M. Day: 18 Month: May Year: 93

Plugging proposal received from: Richard McEntire

Company: Kelso Casing Pulling, Inc. Phone: 316-938-2943

Were: Ordered 200 sxs. 60/40 posmix - 6% gel. and 4 sx. gel.
Plug while pulling casing.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 1:35P.M., Day: 18, Month: May, Year: 93

Actual plugging report: 8 5/8" to 320'. 5 1/2" to 3624'. Sand back
to 3375' and spot 5 sxs. cement with dump bailer. Shot and pulled
2225' of casing. Pulled to 1586' and mixed and displaced 35 sxs. cement
to 1450' to balance plug. Pulled casing to 770' and mixed and pumped
4 sxs. gel in 10 bbls. water, followed by 25 sxs. cement and displaced to
660' to balance cement plug. Pulled casing to 360' and pumped 85 sxs.
cement with cement circulated to surface. Pulled casing and topped with
25/ sxs. cement.

Remarks: Allied Cementing.

Condition of casing(in hole):GOOD X BAD Anhy.plugin: YES X NO

Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO

Plugged through TUBING , CASING X. Elevation: 1860

I did observe the plugging.

[Signature]
STATE CORPORATION COMMISSION
RECEIVED
MAY 21 1993

DN (agent)

DATE 5-25-93

INV. NO. 37751

CONSERVATION DIVISION
Wichita, Kansas