

4-060398

5-21

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-009-22,660 0000
110'S.of
NE NE NW /4 SEC. 18, 20 S, 12 W
440 4840 feet from S section line
2310 feet from E section line
2970

Operator license# 4707 Lease Sessler well # 1

Operator: Carl Boxberger Oil, Inc. County Barton

Address: P.O. Box 1604 Well total depth 4197 feet ^{136.40}
Great Bend, Kansas 67530 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 320 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Kelso Casing Pulling, Inc. License# 6050

Address: P.O. Box 347 - Chase, Kansas 67524

Company to plug at: Hour: 10:15A.M Day: 21 Month: May Year: 93

Plugging proposal received from: Richard McEntire

Company: Kelso Casing Pulling, Inc. Phone: 316-938-2943

Were: Order 200 sxs. 60/40 posmix - 6% gel.
Plug while pulling casing.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 1:00P.M., Day: 21, Month: May, Year: 93

Actual plugging report: 8 5/8" to 320'. 5 1/2" to 4196'. Sand back
to 3170' and spot 5 sxs. cement with dump bailer. Shot and pulled 2520'
of casing. Pulled casing to 1588', mixed and displaced 35 sxs. cement
to 1500'. Pulled casing to 760' and mixed 4 sxs. gel in 10 bbls. water
followed by 25 sxs. cement and displaced to 700'. Pulled casing to
360' and circulated cement to surface with 60 sxs. cement. Pulled
casing and topped with 30 sxs. cement.

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: 1855

I did[X] / did not[] observe the plugging.

INVOICED

DATE 6-11-93

INV. NO. 37880

[Signature] JUN 9 1993
RECEIVED
STATE CORPORATION COMMISSION
WICHITA, KANSAS
(agent) CONSERVATION DIVISION
Form CP-2/3hita, Kansas