

8-31

351 R

To: 1 040562
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-22,058-00-00
NW NW SE, SEC. 9, T. 27 S, R. 12 W/E
2310 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5030
Operator: Vess Oil Corporation
Name & Address: 8100 E. 22nd St. N, Bldg. 300
Wichita, KS 67226

Lease Name Hoeme Well # 4-9
County Pratt 138.12
Well Total Depth 4250 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 10 3/4 feet 283

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor L.D. Drilling, Inc. License Number 6039
Address RR 1, Box 183 B, Great Bend, KS 67530

Company to plug at: Hour: 12 p.m. Day: 31 Month: 8 Year: 19 91

Plugging proposal received from Craig Davidson
(company name) L.D. Drilling, Inc. (phone) 316-793-3051

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 674-700'
1st plug at 700' with 50 sx cement, 2nd plug at 310' with 75 sx cement,
3rd plug at 40' with 20 sx cement,
4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 2 p.m. Day: 31 Month: 8 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 700' with 50 sx cement,
2nd plug at 310' with 75 sx cement,
3rd plug at 40' with 20 sx cement,
4th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

SEP 05 1991

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED (XXXXX did not) observe this plugging.

Signed Steve Pfeifer (TECHNICIAN)

DATE 9-13-91
INV. NO. 33118