

To: 1 040547
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

6-19
API NUMBER 15- 151-22,023-00-00171 R
NE NE SE, SEC. 9, T 27 S, R 12 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 5046

Operator: Raymond Oil Company, Inc.
Name & Address P.O. Box 48788
Wichita, KS 67201

2310 feet from S section line

330 feet from E section line

Lease Name Hoeme Well # 1

County Pratt 145.92

Well Total Depth 4490 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 10 3/4 feet 250

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 4 p.m. Day: 19 Month: 6 Year: 19 91

Plugging proposal received from Ron Casey

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 4460' with 200 sx cement, Perfs at 4352-56, 4152-4206, 4110-18, 3738-46'

1st plug sand back to 3780' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls and

150 sx cement.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5 p.m. Day: 19 Month: 6 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 3680' and dumped 5 sx cement on top
of sand bridge through bailer,

2nd plug pumped down 10 3/4" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 100 lbs. hulls and 150 sx cement.

Maximum pressure 700 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2700' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

~~old~~ observe this plugging.

DATE JUL 19 1991

INV. NO. 32312

Signed Stephen J. Piper
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION

JUN 26 1991

CONSERVATION DIVISION
Wichita, Kansas