

To: 1 040430  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

6-19  
API NUMBER 15- 151-21,592-0001  
NW NW NE, SEC. 8, T 27 S, R 12 W/E  
4950 feet from S section line  
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 9582  
Operator: Studer Oil Company  
Name & Address: P.O. Box 925  
Pratt, KS 67124-0925

Lease Name L.E. Studer Well # 1.OWWO  
County Pratt 145.60  
Well Total Depth 4480 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 10 3/4 feet 287

Abandoned Oil Well  Gas Well  Input Well  SHD Well  D&A   
Other well as hereinafter indicated

Plugging Contractor Pratt Well Service, Inc. License Number 5893  
Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 2:15 p.m. Day: 19 Month: 6 Year: 19 90

Plugging proposal received from Bruce Wagner

(company name) Pratt Well Service, Inc. (phone) 316-672-2531

were: 4 1/2" at 4480' PBTD 4177' Perfs at 4140-60'

1st plug sand back to 4090' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump 400 lbs. hulls, 15 sx gel, 60 sx cement, 13 sx gel, 1 sx hulls, release  
10 3/4" wiper plug and pump 175 sx cement.

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 3 p.m. Day: 19 Month: 6 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 3940' and dumped 4 sx cement on top of  
sand bridge through bailer,

2nd plug pumped down 10 3/4" surface pipe with 300 lbs. hulls, 15 sx gel, 60 sx cement,  
13 sx gel, 200 lbs. hulls and 175 sx cement.

Maximum pressure 125 psi and shut in 50 psi.

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 27 1990

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2080' of casing.  
(if additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 7-3-90  
INV. NO. 28526

Signed Stephen J. Pfeifer  
(TECHNICIAN)