

1 010133

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,765-00-00

SE NE NE, SEC. 8, T 27 S, R 12 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 6408

4290 feet from S section line

330 feet from E section line

Operator: W. K. Black, Inc.

Lease Name Dietz C Well # 1

Name & Address: P. O. Box 801

County Pratt 143.00

Well Total Depth 4400 feet

Pratt, KS 67124

Conductor Pipe: Size _____ feet

Surface Casing: Size 10 3/4" feet 240

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A x

Other well as hereinafter indicated _____

Plugging Contractor Aldebaran Drilling Co., Inc. License Number 5829

Address P. O. Box 18611, Wichita, KS 67218

Company to plug at: Hour: 5:50 am Day: 11 Month: May Year: 19 86

Plugging proposal received from Wayne Bougner

(company name) Aldebaran (phone) 316-685-5372

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 1854'
1st plug in the Arbuckle with 40 sx cement if 50' or more Anhydrite N/A

2nd plug at the base of the Anhydrite with 50 sx cement

3rd plug 30' below the base of the surface pipe with 40 sx cement

4th plug from 40' to surface with 10 sx cement

5th plug to circulate rat hole with 10 sx cement, 6th plug to circulate mouse hole with 10 sx cement Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 7:20 am Day: 11 Month: May Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 690' with 50 sx cement, 2nd plug at 280' with 40 sx cement, 3rd plug from 40' to surface with 20 sx cement. 4th plug to circulate rat hole with 10 sx cement, 5th plug to circulate mouse hole with 10 sx cement. Plugged water well with 10 sx cement.

STATE CORPORATION COMMISSION

MAY 19 1986

Remarks: Used 60/40 Pozmix by Halliburton.

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this form.)

INVOICED
MAY 20 1986

DATE _____

Signed Joseph R. [Signature]
(TECHNICIAN)

INV. NO. 13928