

To: 1 120826
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

9-20
API NUMBER 15- 151-21,831-00-00
85' N & 140' W of
SW SE SE, SEC. 5, T 27 S, R 12 W/E
415 feet from S section line
1130 feet from E section line
Lease Name Dikeman Well # 1
County Pratt 142.35
Well Total Depth 4380 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 357

TECHNICIAN'S PLUGGING REPORT
Operator License # 3180
Operator: Deutsch Oil Company
Name:
Address 107 N. Market, Ste. 1115
Wichita, KS 67202

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor DS&W Well Servicing Co. Inc. License Number 6901
Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 9 a.m. Day: 20 Month: 9 Year: 19 93

Plugging proposal received from Kent Deutsch
(company name) Deutsch Oil Company (phone) 316-267-7551

were: 4 1/2" at 4380' with 125 sx cement, Perfs at 4121-55'
1st plug sand back to 50' above perfs and dump 4 sx cement on top of sand through bailer.
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 100 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 10:30 a.m. Day: 20 Month: 9 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 4070' and dump 4 sx cement on top of sand through bailer,
2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"
wiper plug and pumped 100 sx cement.

Pumping pressure 0-400 psi and shut in 200 psi.

RECEIVED
STATE CORPORATION COMMISSION
SEP 29 1993

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1999' of 4 1/2" casing.
Additional description is necessary, use BACK of this form.)

DATE (did 19-9-93 observe this plugging.)

INV. NO. 38843

Signed Duane Rankin (TECHNICIAN)

9-20