

1 030526

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,394 - 00-00
150' W of C
E/2 W/2 SE, SEC. 5, T 27.S, R 12 W/4

1320 feet from S section line
1800 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5087
Operator: Texas Energies, Inc.
Name & Address: P. O. Box 947
Pratt, KS 67124

Lease Name Dikeman Well # 1-5
County Pratt 145.44
Well Total Depth 4475 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 382

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050
Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 12:30 pm Day: 17 Month: September Year: 19 85

Plugging proposal received from Mark McCabe
(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4439' PBTD 4300' Perfs at 4151-61' 4360-68' 4310.5-14.5'
1st plug sand back to 4100' and dump 4 sx cement on top of sand through bailer
2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,
release 8 5/8" rubber plug and pump 150 sx cement

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1:30 pm Day: 17 Month: September Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4100' and dumped 4 sx cement on top of
sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10
sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 150 sx cement

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 3015' 4 1/2" casing
(if additional description is necessary, use BACK of this form.)

RECEIVED

SEP 23 1985

INVOICED

observe this plugging.

Signed Steve Stewart
(TECHNICIAN)

CONSERVATION DIVISION
Wichita, Kansas

DATE SEP 25 1985
INV. NO. 10264