

15-009-06916-0000

DISTRICT CONSERVATION AGENT'S REPORT

B

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION NE-SE-22W

SEC. 18 TWP. 20 RGE. 12W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 4 Lease Kuehka Huschka

Operator The Bay Pitero Co. Inc. Address #513 - Chase - Kans.

Field _____ County Barton

Total Depth 3562 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2" - 253 ft. Circulated with cement.
5 1/2" casing set at 348 ft. 150 sacks of cement.
Lower Well Plug at 3220 ft. sand to 3200 ft.
Dumped 15 sacks of cement at 3200 ft. - Shot off
9" bitting the 5 1/2" casing - mud to 250 ft. - Set
140 lb bridge & 20 sacks of cement at 250 ft. -
mud to 15 ft. - Plug & 10 sacks of cement
at the surface

PLUGGING
FILE SEC 18 TWP 20 R 12W
BOOK PAGE 58 LINE 8

RECEIVED
STATE CORPORATION COMMISSION
NOV 10 1952
11-10-52
CONSERVATION DIVISION
Wichita, Kansas.

C. H. Stovall
District Conservation Agent
Date 11-7-52