



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. - 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 21 1968
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Bob Herrin of H-30 Drilling, Inc. has this date requested permission to plug the following described well:

Mr. Clinton Oil Company guarantees payment of the plugging fee.

Operator's full Name: Clinton Oil Company

Complete Address: 6810 W. Highway 54, Wichita, Kansas 67202

Lease Name: Batchman Well No. 3-D

Location: SW NE NE Sec. 18 Twp. 20 Rge. 12 (E)(W) W

County: Barton Total Depth 3488 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Bob Herrin was instructed to plug the well as follows:

8 5/8" 284' Cwc.

Circulated hole with heavy mud to 400', set plug, & displaced 40 sax

cement thru drill pipe. Mud to 280', & displaced 25 sax cement thru

drill pipe. Mud to 40', 1/2 sax hulls, plug, & displaced 10 sax cement

with Sun Cementing Company's pump truck, cementing to base of cellar.

Very truly yours,

Don Leman
 Conservation Division Agent