

State of Kansas



15-009-30435-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
AUG 2 1966  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Jim Lahar of B & B Drlg., Inc. has this

date requested permission to plug the following described well:

Mr. Leo J. Dreiling guarantees payment of the plugging fee.

Operator's full Name: Leo J. Dreiling Oil Company

Complete Address: Victoria, Kansas

Lease Name: Parrish "B" Well No. # 1

Location: NE SW SE Sec. 12 Twp. 20 Rge. 13 (E)(W) W

County Barton Total Depth 3477 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Jim Lahar was instructed to plug the well as follows:

8 5/8" 239' Cwc.  
Circulated hole with heavy mud to 230', set plug with 1/4 sax hulls,  
displaced 25 sax cement thru drill pipe. Mud to 40', 1/2 sax hulls,  
plug, & 10 sax cement, cementing to base of cellar.

Very truly yours,

Don Truman  
Conservation Division Agent