

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

OCT 22 1962

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

I have this date Oct. 17 1962., 1962, authorized
 the following plugging operation:

Operator's full Name: ^{TOEN} Addis Oil Operations.

Complete Address: Box 519 Gt. Bend, Kansas.

Lease Name: Grimes #1 Well No. #1

Location: NW NW SW Sec. 9 Twp. 27S Rge. 12 (E) (W) X

County Pratt Total Depth 4386'

Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Operator was instructed to plug well as follows:

326' of 8 5/8" surface pipe circulated with cement. Hole
filled to 250' with heavy drill mud, 1/4 sack hulls, 1st
cementing plug, 20 sacks cement. Hole filled to 35' with
heavy drill mud, 1/4 sack hulls, 2nd cementing plug and 10
sacks cement to base of cellar. Rat hole bridged and
2 sacks cement.

Very truly yours,


 Conservation Division Agent