

KANSAS

Form CP-3  
Rev. 6-4-68

## STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202API Number 15 - - (of this well)Operator's Full Name Raymond Oil Co., Inc.Complete Address One Main Pl., Suite 900, Wichita, Ks. 67202Lease Name Roberts Well No. 1Location SW SW Sec. 22 Twp. 27 SRge. 12 (E) (W) XCounty Pratt Total Depth 3325Abandoned Oil Well        Gas Well X Input Well        SWD Well        D & A       Other well as hereafter indicated       Plugging Contractor Kelso Casing Pulling.Address Box 176-Chase, Ks. 67524 License No. 683Operation Completed: Hour 1:30 Pm. Day 25 Month 8 Year 1980

The above well was plugged as follows:

301' 8 5/8" casing w/250 sax cement. 4 1/2" casing set at 2722' w/125  
sax cement. Plug back to 2681'-Pref's at 2624 to 34'-Sand back to  
2575'-Top sand w/4 sax mixed cement w/dump bailer-Pull 18 1/2' casing-  
Allied mixed & pumped 8 sax hulls-25 sax gel-125 sax 50/50 posmix  
cement w/4% gel & 3% cc to top of 8 5/8" casing. Shut in w/300# cement

RECEIVED  
STATE CORPORATION COMMISSION

SEP - 2 1980

CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging SupervisorDATE 9-4-80INV. NO. 29984