

To: 1 040688
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

8-18 API NUMBER 15- 151-21,175-00-0921 P
NE NE NW, SEC. 14, T. 27 S, R. 13 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 9232
Operator: Timberline Oil & Gas Corporation
Name &
Address 4447 S. Canyon Rd., Suite 1
Rapid City, SD 57702

4950 feet from S section line
2970 feet from E section line
Lease Name Rolf Well # 1
County Pratt 143.00
Well Total Depth 4400 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 374

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11:15 a.m. Day: 18 Month: 8 Year: 19 92

Plugging proposal received from Darrell Kelso
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

work: 4 1/2" at 4399' w/150 sx cement, PBTD 4399', Perfs at 4347-49'
1st plug sand back to 4300' and dump 4 sx cement on top of sand bridge through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:30 p.m. Day: 18 Month: 8 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 4300' and dumped 4 sx cement on top of sand
bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx
gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 200 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2100' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form)

I (did ~~not~~) observe this plugging.

DATE 8-27-92

WV. NO. 36071

Signed [Signature]
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION

AUG 24 1992

CONSERVATION DIVISION
WICHITA, KANSAS