

State of Kansas

FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

SEP 8 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Doyle Rand of Harms Drilling Company has this
date requested permission to plug the following described well:

Mr. Rand guarantees payment of the plugging fee.

Operator's full Name: Kern-Landes Exploration Co., Inc.

Complete Address: Box 699, Magnolia, Arkansas

Lease Name: Elmer Well No. # 1

Location: NW NE SW Sec. 28 Twp. 27 Rge. 12 (E) (W) W

County Pratt Total Depth 4510 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Rand was instructed to plug the well as follows:

277' of 8 5/8" surface pipe, cement circulated with 225 sacks.
Fill hole with drilling mud to 275', 1st cementing plug, bridge
with hulls, and cement with 25 sacks. Fill hole with drilling
mud to 40', 2nd cementing plug, bridge with hulls, and cement
with 10 sacks to base cellar. Bridge and cement rat hole with
2 sacks.

Very truly yours,

Archie Elving