

State of Kansas

FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION

NOV 12 1963

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Bill Musgrove of Bowers Drilling Co. has this
 date requested permission to plug the following described well:

Mr. Musgrove guarantees payment of the plugging fee.

Operator's full Name: Bowers Drilling Co.

Complete Address: 416 Union Center, Wichita, Kansas

Lease Name: Hamm Well No. # 1

Location: SE SE NW Sec. 35 Twp. 27 Rge. 12 (E) (W) W

County Pratt Total Depth 4533 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Musgrove was instructed to plug the well as follows:

170' of 13 3/8" surface pipe, cemented to top.

Fill hole with drilling mud to 200', 1st cementing plug,

bridge with 1 sack hulls, cement with 50 sacks. Fill hole

with drilling mud to 40', 2nd cementing plug, 1 sack hulls,

cement with 20 sacks. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
 Conservation Division Agent