



15-009-20714-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
FEB 15 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Fred Damme of Red Tiger Drilling Company has this date requested permission to plug the following described well:

Mr. Clinton Oil Company guarantees payment of the plugging fee.

Operator's full Name: Clinton Oil Company

Complete Address: 217 N. Water, Wichita, Kansas 67202

Lease Name: Florence Kutina Well No. 1-V

Location: App. NE SW SW Sec. 8 Twp. 20 Rge. 12 (E)(W) W

County: Barton Total Depth 3520 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Fred Damme was instructed to plug the well as follows:

10 3/4" csg. 300' Cwc.

Circulated hole with heavy mud to 420', set plug, & displaced 50 sax

cement thru drill pipe. Mud to 240' & displaced 30 sax cement thru

drill pipe. Mud to 40', 1 sax hulls, plug, & displaced 15 sax cement

with Sun Cementing Company's pump truck, cementing to base of cellar.

Very truly yours,

Don [Signature]
Conservation Division Agent