

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Budig of Union Drlg., Co., Inc.

RECEIVED
STATE CORPORATION COMMISSION
SEP 14 1979
CONSERVATION DIVISION
Wichita, Kansas

has this date requested permission to plug the following described well

Mr. Budig guarantees payment of the plugging fee.

Operator's full Name: John O. Farmer, Inc.

Complete Address: Box 352 Russell, Ks. 67665

Lease Name: Hoener Well No. 1

Location: C NW NE Sec. 14 Twp. 27s Rge. 13 (E)(W) W

County: Pratt Total Depth 4465 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Budig was instructed to plug the well as follows:

266' of surface pipe. A combination of 12 3/4" & 13 3/8"

casing. Cemented w/250 sax cement on bottom & 100 sax on top

through 1" pipe. Set 50 sax cement plug at 600'-Set 50 sax

cement plug at 240'-Bridge at 35' & 35 sax cement to top of

casing-5 sax in rat hole & 2 sax in water well. Cemented by

Howco.

Very truly yours,

Conservation Division Agent