

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

**RECEIVED**  
STATE CORPORATION COMMISSION

APR 27 1964

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Time Petroleum Company

Complete Address: 815 Union National Bldg., Wichita, Kansas

Lease Name Mott Well No. # 1

Location SE SE NE Sec. 6 Twp. 27 Rge. 13 ( ~~N~~ ) ( W ) W

County Pratt Total Depth 4505

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:   

Plugging Contractor: Leben Drilling Inc.

Address: 905 Central Bldg., Wichita, Kansas License No.                 

Operation Completed: Hour 3:00PM Day 24th Month April Year 1964

The Above well was plugged as follows:

346' of 8 5/8" surface pipe, cemented with 300 sacks. Fluid level was  
up in the hole. 1st cementing plug and 1/2 sack hulls was pushed to 300',  
and cemented with 25 sacks, through the drill pipe. Hole was filled  
with drilling mud to 40', 2nd cementing plug, bridged with hulls, and  
cemented with 10 sacks to base cellar. Rat hole bridged and cemented  
with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**  
DATE 4/28/64  
INV. NO. 9051-W

Signed: Archie Elving  
Well Plugging Supervisor