

DISTRICT CONSERVATION AGENT'S REPORT

*R*

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 140-13

LOCATION G-SW-27E-2E

SEC. 11 TWP. 17 RGE. 13-ew

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 3 Lease Reynolds

Operator The Atlantic Refining Co Address Box #17 - G. Bond - Kans.

Field \_\_\_\_\_ County Pratt

Total Depth 4339 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2" - 388 ft. Circulated with cement.  
5 1/2" casing set at 4339 ft. - 200 sacks of cement.  
Plugged back to 4000 ft. with sand - Mixed 5 sacks of  
cement at 4000 ft. Shot off & pulled the 5 1/2" casing  
and to 300 ft. - Set rock bridge & 15 sacks of  
cement at 300 ft. - and to 35 ft. - Bridge &  
10 sacks of cement at the surface.  
Patterson & Son - Plugging Contractors -

RECEIVED  
CONSERVATION DIVISION

FEB 14 1952

CONSERVATION DIVISION  
Wichita, Kansas

C. H. Stover  
District Conservation Agent

Date 2-13-52

**PLUGGING**  
FILE 15-151-10395-00-00  
PAGE 140