

KANSAS STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED STATE CORPORATION COMMISSION OCT 7 1959 CONSERVATION DIVISION Wichita, Kansas

TO: Jewel M. Ogden, Director 500 Insurance Building 212 North Market Wichita 2, Kansas

File No. 3-16 County: Pratt

Location: NW NW NW Sec. 29 Twp. 27 Rge. 12 (E) (W) ✓

Name of Field: Total Depth: 4445

I have this date completed supervision of plugging of:

Lease Name: Paddock Well No. 1

Operator's Full Name: Sheridan Drilling Co.

Complete Address: 617 Union Center Bldg, Wichita, Kans.

Plugging Contractor: Ace Pipe Pulling Co.

Address: West Bent, Kans. License No. 2 ✓

Oil Well ✓ Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Was any delay in plugging operations caused by Conservation Division Agent? Yes No ✓

If yes how long? Reason:

Operation Completed: Hour 3pm Day 9 Month Sept Year 1959

The above well was plugged as follows:

2 1/2" of 8 5/8" surface casing. Top perf. 3780'. Hole mud filled to 3720 with sand and 5 sacks cement dumped with bit. Pulled 3380' of 5 1/2". Hole filled to 259' with mud. Rock bridge from 259 to 249'. 55 sacks cement dumped. Mud to 40'. Rock bridge from 40' to 30'. Cement poured to base of casing.

Signed: [Signature] Conservation Division Agent

Reviewed: [Signature] Field Supervisor

Remarks:

INVOICED DATE - 2-29-60 INV. NO. - 1-8/60