

Form CP-3  
Rev. 6-26-62KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORTJ. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas.RECEIVED  
STATE CORPORATION COMMISSION  
SEP 8 1964  
CONSERVATION DIVISION  
Wichita, KansasOperator's Full Name Kern-Landes Exploration Company Inc.Complete Address: Box 699, Magnolia, ArkansasLease Name Elmer Well No. # 1Location NW NE SW Sec. 28 Twp. 27 Rge. 12 (E) (W) WCounty Pratt Total Depth 4510Abandoned Oil Well Gas Well Input Well SWD Well D & A XOther well as hereafter indicated: Plugging Contractor: Harms Drilling CompanyAddress: Box 488, Great Bend, Kansas License No. Operation Completed: Hour 10:15AM Day 4th Month Sept. Year 1964

The Above well was plugged as follows:

277' of 8 5/8" surface pipe, cement circulated with 225 sacks. Fluid  
level was up in the hole. 1st cementing plug and 1 sack hulls was  
pushed in fluid to 275', and cemented with 25 sacks, through the drill  
pipe. Hole was filled with drilling mud to 40', 2nd cementing plug,  
bridged solid with hulls, on fluid at 40', and cemented with 10 sacks  
to the base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging SupervisorDATE 9/8/64INV. NO. 9781-14