

KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING SUPERVISOR'S REPORT

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. 81-9 Location: CE/1/4 NE NW

County: Pratt Sec. 4 Twp. 27 Rge. 13 (E) (W) W

Name of Field or Pool: \_\_\_\_\_ Total Depth: 4460

I have this date completed supervision of plugging of:

Well No. 4 Lease Chance

Operator's Full Name Monsanto Chemical Co.

Complete Address: Box 580, Pratt, Kans.

Plugging Contractor: West Supply

Address: Chase, Kans. License No. 14

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

If well is a rotary drilled dry hole did operators wait for you to arrive \_\_\_\_\_

If yes how long \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 10A.M. Day 15 Month February Year 1958

The above well was plugged as follows:

802' of 85/8" casing, circulated with 450 sack of cement. 4340 feet  
of 5 1/2" circulated with 250 sack of cement. Perf. 4302-10, in Viola.  
Hole was sanded above perforations to 4300. 5 sack of cement was dumped  
with dump bailed on sand. Hole was mudded with heavy jell mud to 350'.  
Rock bridge and 20 sack cement at 350'. Mud to 35' with rack bridge at  
35' with 10 sack cement to surface. XX

I hereby certify that the above well was plugged as herein stated and that I was present while the above well was being plugged.

Signed:   
Well Plugging Supervisor

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED  
DATE FEBRUARY 15 1958

FEB 20 1958

CONSERVATION DIVISION  
Wichita, Kansas

Reviewed:   
Field Supervisor

Signed: \_\_\_\_\_  
Well Plugging Supervisor

Remarks:

PLUGGING  
FILE SEC 4 T 27 R 13W  
BOOK PAGE 81 LINE 9