

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

NOV 8 1965

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Kern-Landes Exploration Compnay
 Complete Address: 337 Union Center, Wichita, Kansas
 Lease Name Lunt Well No. # 1
 Location C NW NW Sec. 33 Twp. 27 Rge. 12 (E) (W) W
 County Pratt Total Depth 4491'
 Abandoned Oil Well X Gas Well Input Well SWD Well D & A
 Other well as hereafter indicated:
 Plugging Contractor: Knight Casing Pulling Company
 Address: Box 405, Chase, Kansas License No. 436
 Operation Completed: Hour 4:00 PM Day 7th Month Nov. Year 1965

The Above well was plugged as follows:

275' of 8 5/8" surface pipe cement circulated. 4485' of 4 1/2" long string,
cemented with 250 sacks. Top perferation 4452'. Bottom of the hole was
sanded to 4450', and cemented with 3 sacks. 3206' of 4 1/2" long string was
recovered from the hole. Fluid was up in the hole. Bridge plug was pushed
in fluid to 260', rock bridge from 260' to 250'. 1 sack of Cal-Seal was
mixed in barrel and put on plug at 250', and let set for 2 hours. Hole
was bailed dry, and 25 sacks of cement was added to the plug. Hole was
filled with drilling mud to 40', rock bridge from 40' to 30', and cemented
with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Achie Cling
Well Plugging Supervisor

INVOICED

DATE 11/9/65

W.P. NO. 2143-W