

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Barton County. Sec. 23 Twp. 17S Rge. 15 XX (W)

Location as "NE/CNW&SW" or footage from lines Gen. S/2 NW NW

Lease Owner Three G Oil, Inc.

Lease Name Benedict Axman "A" Well No. 1

Office Address 1101 Wichita Plaza Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed October 30 19 66

Application for plugging filed Verbal Authority 19

Application for plugging approved Verbal Authority 19


Plugging commenced October 30 19 66

Plugging completed October 30 19 66

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Donald Truan

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3472 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE (IN)	DEPTH (IN)	PULLED OUT
				8-5/8"	945'	None
				NOV 7	1966	Rec'd
					11-0	-660

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 3472' (rotary total depth) to 350'. Set bottom plug @ 350' and cemented with 25 sacks cement and 1/2 sack hulls. Filled hole with heavy rotary mud to 40'. Set top plug @ 40' and cemented with 10 sacks cement and 1/2 sack hulls; 5 sacks cement in rat hole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor H-30, Inc.

Address 200 No. Main, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. Arlo B. Romer (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Arlo B. Romer

200 No. Main, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of October, 1966

Dona B. Webber
Dona B. Webber Notary Public.

My commission expires May 4, 1967

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS


COMPANY Three G Oil, Inc.

SEC. 23 T. 17S R. 15W
 LOC. Cen. S/2 NW NW

FARM Benedict Axman "A" NO. 1

TOTAL DEPTH 3472'
 COMM. 10/19/66 COMP. 10/30/66
 SHOT OR TREATED
 CONTRACTOR H-30, Inc.
 ISSUED

COUNTY Barton
 KANSAS



CASING

20	10
15	8 - 5/8" @ 945' w/425 sx. cement
12	6
13	5

ELEVATION 1913 K.B.

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Top soil	20
Post Rock	45
Shale	130
Sand	140
Shale	405
Sand	445
Shale	515
Shells, Red Bed & Shale	800
Shells & Shale	935
Anhydrite	957
Shale & Red Bed	1220
Shale & Shells	1650
Shells & Shale	1700
Shale w/Broken Lime	1850
Shale & Lime	2027
Lime & Shale	2150
Shale & Lime	2635
Shale & Lime Streaks	2865
Lime & Shale	3077
Lime	3472
Rotary T. D.	3472

ELECTRIC LOG TOPS:

Anhydrite Top	929	+ 984
Anhydrite Base	955	+ 958
Topeka	2897	- 984
Heebner	3133	-1220
Toronto	3149	-1236
Douglas	3164	-1251
Lansing K.C.	3197	-1284
Base K.C.	3422	-1509
Reworked Arbuckle	3453	-1540
Arbuckle	3456	-1543
Log T. D.	3471	-1558
Rotary T. D.	3472	-1559

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 1 1966

I hereby certify the above and foregoing to be true and correct log of the above described well, as shown by the drilling reports.

H-30, INC.

By Arlo B. Romer
 Arlo B. Romer

STATE OF KANSAS)
) ss.
 SEDGWICK COUNTY)

Subscribed and sworn to before me, a Notary Public in and for said county and state, this 31st day of October, 1966.

Dona B. Webber
 Dona B. Webber, Notary Public

My Commission Expires:
 May 4, 1967