


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittig Building  
Wichita, Kansas

Barton County, Sec. 8 Twp. 20 Rge. 12 (E) (W)

NORTH



Locate well correctly on above  
Section Plat

Location as "NE/CNW%SW%" or footage from lines NW SW NE  
Lease Owner Carl W. Boxberger  
Lease Name Lanterman Well No. 1  
Office Address Box 474 - Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 7-5 19 58  
Application for plugging filed 7-5 19 58  
Application for plugging approved 19  
Plugging commenced 11:00 AM 7-6 19 58  
Plugging completed 1:00 AM 7-6 19 58  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well  
Producing formation Depth to top Bottom Total Depth of Well Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Ran 312.44 ft of used with 225 sx Pozmix Cement		8 5/8"	Casing.	Cemented same @ 308'	
				w/2% c.c. Cement	circulated.	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole to 275' w/heavy drilling mud.  
Set plug - 1/4 sx cotton seed hulls and 25 sx cement  
through drill pipe at 275' - finished filling hole.  
With mud to 40' - set plug - 1/4 sx cotton seed hulls  
and 10 sx cement

ST4  
COMMISSION  
JUL 10 1958 07-10-58  
COMMISSION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Ari-Kan Drilling Company  
Address Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
Carl W. Boxberger (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Carl W. Boxberger  
P.O. Box 474 - Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of July, 19 58

My commission expires April 1, 1959

Wanda Nichols  
Notary Public.

PLUGGING  
FILE SEC B.T. 20 R 12W  
BOOK PAGE 114 LINE 33

Company-- Carl W. Boxberger  
Farm -- Lanterman No. 1

Sec. 8-20-12  
NW SW NE

Total Depth-- 3472'  
Comm. 6-24-58 Comp. 7-5-58  
Contractor-- Ari-Kan Drilling Company

County - Barton  
Elevation-- 1854 DF  
1851 Gr

Casing 8 5/8" 308'

Figures indicate Bottom of Formations

Sand and shell	165'
Hard Sand	185
Sand and shale	252
Shale	309
Shale and shell	340
Red Bed	450
Red Bed	600
Shale and shells	680
Anhydrite	710
Shale and Shells	950
Shale and shells and Salt	1360
Shale and shells	1560
Lime and shale	1580
Lime	1920
Lime and shale	2045
Shale and Lime	2210
Shale and shells	2385
Shale and Lime	2565
Lime and shale	2650
Shale and shell	2705
Lime	2745
Lime	3088
Douglas shale	3130
Shale and Lime	3170
Lime	3445
Lime arbuckle	3472

RECEIVED  
STATE OF KANSAS  
COMMISSION

JUL 10 1958

COMMISSION DIVISION  
Wichita, Kansas

PLUGGING

FILE SEC B. T. 20 R12W  
BOOK PAGE 114 LINE 33