

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

#4
API NUMBER 15-009-14484-0000

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE NAME Schartz

WELL NUMBER #2

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 7 TWP. 20 SRGE. 12 W (E) or (W)

COUNTY Barton

Date Well Completed 2-25-49

Plugging Commenced 6-15-88

Plugging Completed 7-13-88

LEASE OPERATOR Knighton Oil Co., Inc.

ADDRESS 710 Petroleum Bldg.
Wichita, Kansas 67202

PHONE # (316) 264-7918 OPERATORS LICENSE NO. 5010

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #2 Wichita, Kansas

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3435'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	365'	none
				5-1/2"	3433'	405'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged off bottom with sand to 3120' and 5 sacks cement. Shot pipe @2600', pipe parted @405', pulled a total of 13 joints of 5-1/2" casing. Plugged surface with 4 hulls, 10 gel, 50 cement, 10 gel, 1 hull, 8-5/8 plug, 125 sacks cement, 60/40 pos., 6% gel. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) *Mike Kelso*

(Address) Box 347
Chase, Kansas 67524

RECEIVED
STATE CORPORATION COMMISSION
AUG - 5 1988

CONSERVATION DIVISION
Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 3rd day of August, 19 88

IRENE HOOVER
State of Kansas
My Appt. Exp. Aug. 15, 1989

Irene Hoover
Notary Public

Commission Expires:

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

COPY


Company. HANLON-BOYLE, INC.
Farm - Scharke No. 2

SEC. 7 T. 20 R. 12W
SE SW SW

Total Depth. 3437'
Comm. 1-14-49 Comp. 2-4-49
Shot or Treated.
Contractor. L-S-T Drlg. Co.
Revised. 3-12-49

County. Barton

KANSAS



CASING:
8-5/8" 365' 5 1/2" 3433'

Elevation. _____

Production. Pot. 3677 bbls.

Figures Indicate Bottom of Formations.

sand & surface clay	95
shale	125
sand & iron	130
iron pyrite	139
shale & shells	366
red bed	665
anhydrite	690
red bed	810
shale & shells	1157
salt & shale	1210
salt	1395
salt & shale	1425
shale & shells	1455
lime & shale	1510
lime brkn	1614
lime	1680
lime brkn	1760
lime	2105
lime & shale	2190
shale & shells	2555
shale	2599
lime & shale	2715
lime	3060
lime & shale	3090
lime brkn & shal	3156
shale & lime	3208
lime	3211
lime & shale	3240
lime	3437
Total Depth	

Tops:	
Heebner	3048
Brwn Lime	3166
Lansing	3182
Arbuckle	3432

K. G. S. LIBRARY