

15-009-00044-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging of formations.

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Barton County, Sec. 12 Twp. 9S Rge. 13 ~~XX~~ (W)
Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE NE SW
Lease Owner Hanlon-Boyle, Inc.
Lease Name Proesser Well No. 1
Office Address Box 1559, Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 1 19 52
Application for plugging filed June 17 19 52
Application for plugging approved June 19 19 52
Plugging commenced June 19 19 52
Plugging completed June 25 19 52
Reason for abandonment of well or producing formation Dry hole to Arbuckle Lime.



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production ~~XX~~ 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough
Producing formation Arbuckle Depth to top 3470' Bottom ~~XX~~ Total Depth of Well 3487' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Heebner		3098				
Brown Lime		3202				
Lansing		3218				
Conglomerate		3460				
Arbuckle	Water	3470				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back from total depth 3487' to 3366', or 15' into the 5 $\frac{1}{2}$ " casing.

Dumped 5 sacks of cement. Shot casing off at 2700'. Pulled casing.

Filled hole with heavy mud to bottom of surface pipe at 240'.

Squeezed 75 sacks of Halliburton cement.

REC'D
07-11-50

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to Hanlon-Boyle, Inc. Conservation Division
Address Box 1559, Tulsa, Oklahoma (Wichita, Kansas)

STATE OF Oklahoma, COUNTY OF Tulsa, ss.
C. F. Wolfe (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-
described well as filed and that the same are true and correct. So help me God.

(Signature) *C. F. Wolfe*
HANLON-BOYLE, INC.
Box 1559, Tulsa, Oklahoma
(Address)

SUBSCRIBED AND SWORN to before me this 9 day of July, 19 52.

C. S. Gardner

My commission expires 2-17-55

Notary Public.

PLUGGING
FILE SEC 12-19R (30)
BOOK PAGE 24 LINE 27

WELL LOG

SIMON IEBOW

Elevation: 1887 R.B.

Contractor: Quaker Drilling Co., Inc.

Commenced: 5-7-52

No. 1 Prosser
NE NE SW Sec. 12-19S-13W
Barton County, Kansas

Completed: 5-18-52

Production:

Casing Record:

Set 240' of 8-5/8" w/150 sacks

(Figures indicate bottom of formation)

FORMATION:

FORMATION TOPS

Surface Clay & shale	160
Sand and Shale	240
Sand	275
Sand and Shale	390
Red Bed & Shale	772
Anhydrite	800
Shale & Shells w/streaks of sand and pyrites	1260
Lime and Shale	2220
Lime, Shale & Shells	2530
Lime and Shale	3288
Lime	3315
Lime and Shale	3481 T.D.


Heebner	3098	--1211
Brown Lime 3	3202	-1315
Lansing 3	3218	-1331
Conglomerate	3460	-1573
Arbuckle	3470	-1583
T.D. (c)	3480	-1593

I hereby certify that the above is a true and correct copy of
Drillers Log of well drilled in the NE NE SW of Section 12,
Township 19 South, Range 13 West, Barton County, Kansas.

QUAKER DRILLING CO., INC.

By: _____

Subscribed and sworn to before me this _____ day of _____, 1952.

Notary PublicMy commission expires:
March 7, 1955**RECEIVED**
STATE CORPORATION COMMISSION

JUL 18 1952

CONSERVATION DIVISION
Wichita, Kansas