


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

15-009 - 00207-0000
WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines Barton County. Sec. 18 Twp. 19 Rge. 12 (W)
C-NW NW NE
Lease Owner Sunray Oil Corporation
Lease Name Hermes Well No. 1
Office Address Box 195, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 5-20 19 52
Application for plugging filed 5-21 19 52
Application for plugging approved 5-22 19 52
Plugging commenced 5-27 19 52
Plugging completed 5-30 19 52
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough
Producing formation None Depth to top Bottom Total Depth of Well 3147' Feet
Show depth and thickness of all water, oil and gas formations. PB 3238 $\frac{1}{2}$ '

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Lansing	Water	3175	3351	5-1/2"	3361'	2811'
				8-5/8"	221'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded hole from 3242' to 3220' and ran 5 sax of cement. Bailed hole & mudded hole from 3190' to 221'. Set rock bridge from 221' to 240' and ran 20 sax of cement. Mudded hole to 40' and ran 10 sax of cement. Plugging completed.

RECEIVED
STATE CORPORATION COMMISSION

JUN 12 1952 10-12-52

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Company
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
W. E. Westbrook, Jr. (employee of owner) or owner or operator of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. E. Westbrook, Jr. Engineer

Box 195, Great Bend, Kansas
(Address)


SUBSCRIBED AND SWORN TO before me this 11th day of June, 19 52

Martha Scott

Notary Public.

My commission expires April 19, 1956

23-8390-s 6-51-20M



Sunray Oil Corporation
Tulsa, Oklahoma

Tulsa, Oklahoma
May 6, 1952

CONTRACTOR: Stickle Drilling Company
Drilling commenced: April 18, 1952
Drilling completed: May 1, 1952

M. O. Hermes #1 NW-NW-
NE-Section 18-19S-12W,
Barton County, Kansas

DRILLERS LOG

Surface Clay	0-130
Shale & Shells	130-222
Iron	222-260
Shale	260-520
Red Bed	520-720
Anhydrite	720-735
Shale & Shells	735-1285
Shale & Lime	1285-1690
Lime & Shale	1690-1920
Broken Lime	1920-2027
Shale & Lime	2027-2295
Shale & Shells	2295-2455
Lime & Shale	2455-2535
Lime	2535-2645
Shale & Lime	2645-2775
Lime & Shale	2775-2975
Lime	2975-3447 TD

I, Frank E. Stickle hereby certify the above to be a complete and true drillers log of Sunray Oil Corporation's M.O. Hermes #1 NW-NW-NE-Section 18-19S-12W, Barton County, Kansas.

Frank E. Stickle
Frank E. Stickle

Lillian T. Bonham
Notary Public

February 13, 1956
My commission expires

PLUGGING	
FILE SEC	18 T 19 R 14
BOOK	PAGE 18 LINE 1

RECEIVED
STATE CORPORATION COMMISSION
JUN 12 1952
CONSERVATION DIVISION
Wichita, Kansas