


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

15-009-20088-0000
WELL PLUGGING RECORD

Barton County. Sec. 23 Twp. 17S Rge. 15(W)

Location as "NE/CNW/SW" or footage from lines NE NW SW
Lease Owner Jay-Bee Oil Company, Inc.
Lease Name Boor Well No. 2
Office Address 515 Union Center Bldg., Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 25 1967
Application for plugging filed Verbal Approval 19
Application for plugging approved Verbal Approval 19
Plugging commenced August 25 1967
Plugging completed August 25 1967
Reason for abandonment of well or producing formation _____

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	291'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 3,556 feet (rotary total depth) to 295 feet. Squeezed 85 sacks cement from 295 feet to cellar, 2 sacks in rat hole.

RECEIVED
STATE CORPORATION COMMISSION

AUG 30 1967

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor H-30, Inc.
Address 200 North Main Street, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Arlo B. Romer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Arlo B. Romer
200 North Main Street, Wichita, Kansas
67202 (Address)

SUBSCRIBED AND SWORN to before me this 29th day of August, 1967

My commission expires April 21, 1971

Martha Hartpence
Martha Hartpence Notary Public.

KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

97

COMPANY Jay Bee Oil Company, Inc.

SEC. 23 T. 17S. 15W
 LOC. NE NW SW


FARM Boor NO. 2

TOTAL DEPTH 3,556'
 COMM. August 16, 1967

COMP. August 25, 1967

COUNTY Barton

SHOT OR TREATED
 CONTRACTOR H-30, Inc.
 ISSUED



CASING

20	10		
15	8	-5/8 291' cemented w/200 sks cement	ELEVATION 1975 KB
12	6		
13	5		

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Top Soil	14
Post Rock	67
Shale & Shells	289
Shale	450
Sand	620
Shale	997
Anhydrite	1034
Shale	1330
Shale & Lime	1840
Shale	1990
Lime	2200
Lime & Shale	2375
Lime	2390
Shale & Lime Streaks	2580
Shale & Lime	2937
Lime	3120
Lime & Shale	3223
Lime	3556
Rotary Total Depth	3556

ELECTRIC LOG TOPS:

Heebner	3191	-	1216
Toronto	3206	-	1231
Lansing	3255	-	1280
Base K.C.	3496	-	1521
Arbuckle	3520	-	1545
Log T.D.	3550	-	1575
Rotary T.D.	3556	-	1581

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 29 1967
 CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify the above and foregoing to be a true and correct log of the above described well, as shown by the drilling reports.

H-30, INC.

Arlo B. Romer

 Arlo B. Romer

STATE OF KANSAS }
 COUNTY OF SEDGWICK } SS:

Subscribed and Sworn to before me a Notary Public in and for said County and State, this 29th day of August, 1967.

Martha Hartpence

 Martha Hartpence - Notary Public

My Commission Expires - April 21, 1971