

WELL PLUGGING RECORD

Get All Information Completely
The Required Affidavit
Filed or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Pratt County, Sec. 6 Twp. 27 Rge. 13 (E) (W)

Location as "NE/CNW/SW" or footage from lines SE SE NE

Lease Owner Time Petroleum Company

Lease Name Mott Well No. 1

Office Address 815 Union National Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 4-24-64 19

Application for plugging filed 4-24-64 19

Application for plugging approved 4-24-64 19


Plugging commenced 4-24-64 19

Plugging completed 4-24-64 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well Archie Elving, Pratt, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4505 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	346.68'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with Mud to 300' Plug & 1/2 sk. hulls 25 sacks cement through the drill pipe.
Mud to 40' Plug 1/4 sk. hulls & 10 sacks cement.
2 sacks in rathole.

RECEIVED
STATE CORPORATION COMMISSION

APR 28 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.

Address P. O. Box 486, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.

Leslie Kite (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite

P. O. Box 486, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of April, 1964

My commission expires April 1, 1967

Ulanda Nichols
Notary Public.

DRILLER'S LOG

COMPANY: Time Petroleum Company
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: MOTT #1
 LOCATION: SE SE NW Sec. 6-27-13
 PRATT COUNTY, KANSAS
 COMMENCED: 4-13-64
 COMPLETED: 4-24-64

0	135	Sand
135	160	Shale & Clay
160	200	Sand
200	300	Sand & Shale Streaks
300	347	Redbed
347	842	Shale & Redbed
842	874	Anhydrite
874	1900	Shale & Shells
1900	2025	Shale & Lime
2025	2204	Lime & Shale
2204	2330	Shale & Lime
2330	2530	Lime & Shale
2530	3050	Shale & Lime
3050	3855	Lime & Shale
3855	3890	Shale & Lime
3890	4035	Lime & Shale
4035	4165	Shale & Lime
4165	4210	Lime & Shale
4210	4270	Lime
4270	4311	Lime & Shale
4311	4370	Lime
4370	4400	Chert & Lime
4400	4465	Lime & Chert
4465	4505	Lime, Shale & Sand
	<u>4505</u>	<u>Rotary Total Depth - D. & A.</u>

RECEIVED
 STATE CORPORATION COMMISSION

APR 28 1964

CONSERVATION DIVISION
 Wichita, Kansas

Set 8 5/8" used surface casing @ 346.68' with landing joint cemented with 300 sacks Common with 2% Gel. 2% c.c.

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Mott #1 well, located SE SE NE of Section 6, Township 27, Range 13, Pratt County, Kansas, as reflected by the files of Leben Drilling, Inc.

Leslie Kite
 Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 27th day of April, 1964.

Ulanda Nichols
 Ulanda Nichols, Notary Public

My Commission Expires:
 April 1, 1967