

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Pratt

County. Sec. 8 Twp. 27 Rge. (E) 13 (W)

Location as "NE/CNW/SW" or footage from lines Ctr. SW/4 NW/4 NW/4

Lease Owner Lion Oil Company

Lease Name Airport Well No. 2

Office Address P. O. Box 639, Pratt, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 3-7 19 53

Application for plugging filed 3-24 19 53

Application for plugging approved 3-25 19 53

Plugging commenced 3-30 19 53

Plugging completed 4-1 19 53

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Merle Rives

Producing formation Depth to top Bottom Total Depth of Well 4545 Feet

Show depth and thickness of all water, oil and gas formations. Plugged back total depth 3890'.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	863'	0'
				5-1/2"	4544'	3224'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Rocked hole from 3890' to 3855' and ran 5 sacks of cement. Halliburton pumped in 25 sacks of Aquagel and 100 sacks of cement to complete plugging.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Company

Address Chase, Kansas

STATE OF KANSAS, COUNTY OF PRATT, ss.

Vernon Hayes (employee of owner) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Vernon Hayes

P. O. Box 639, Pratt, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 4th day of April 19 53

My commission expires August 29, 1955

Don Daubek Notary Public.

RECEIVED STATE CORPORATION COMMISSION

APR 6 - 1953

CONSERVATION DIVISION Wichita, Kansas

PLUGGING FILE SEC 8 T 27 R 13 W BOOK PAGE 87 LINE 12

SW-NW-NW
 SEC. 8-27s-13w
 PRATT COUNTY, KANSAS

AIRPORT WELL No. 2

CONTRACTOR: THE R. W. RINE DRILLING COMPANY
 STARTED: FEB. 4, 1953 FINISHED: FEB. 24, 1953

LOG

SURFACE SAND	0	678	
CLAY & RED ROCK	678	870	8 5/8" @ 863' w/240 SX & 63' SX STRATOCRETE & 100 SX COMMON
SHALE	870	1820	
SHALE & LIME	1820	3760	SYFO @ 1073' - 1/0
SHALE & LIME BROWN	3760	3850	SYFO @ 1500' - 1/0
LIME	3850	3885	SYFO @ 1900' - 3/4 0
LIME & SHALE	3885	3920	SYFO @ 2500' - 1/0
LIME	3920	3960	SYFO @ 3000' - 3/4 0
LIME & SHALE	3960	4010	SYFO @ 3500' - 1/0
LIME	4010	4250	SYFO @ 4100' - NG
CHERTY LIME	4250	4316	SYFO @ 4330' - 1 3/4 0
LIME, CHERT & SHALE	4316	4335	
CHERTY LIME	4335	4345	
LIME	4345	4370	
LIME & CHERT	4370	4405	
CORE #1	4405	4435	
CORE #2	4435	4460	
SHALE & LIME	4460	4545	TD 5 1/2" CASING @ 4544' w/200 SX POSMIX

I, R. M. GREEN, DO HEREBY CERTIFY THAT THE ABOVE IS A TRUE AND ACCURATE LOG OF THE AIRPORT WELL No. 2, LOCATED SW-NW-NW, SECTION 8-27s-13w, PRATT COUNTY, KANSAS

R. M. Green
 ASSISTANT SECRETARY

SUBSCRIBED TO AND SWORN BEFORE ME THIS 4th DAY OF MARCH, 1953.

Leona T. Pederson
 NOTARY PUBLIC

MY COMMISSION EXPIRES APRIL 20, 1955.

RECEIVED
 COMMISSION
 25 1953

PLUGGING
 FILE SEC 8 T 27 R 132
 BOOK PAGE 22 LINE 12