


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Pratt County, Sec. 9 Twp. 27 Rge. (E) 13 (W)

Location as "NE/CNWxSWx" or footage from lines NE 1/4 NE 1/4 NE 1/4
Lease Owner Durbin Bond & Co., Inc., and Lewis Drilling Company
Lease Name City of Pratt Well No. 1
Office Address 915 Union Center, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed November 25 19 56
Application for plugging filed November 25 19 56
Application for plugging approved November 27, 1956 19
Plugging commenced November 25 19 56
Plugging completed November 25 19 56
Reason for abandonment of well or producing formation dry



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? _____

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4571 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	592'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Run heavy mud to 300', drove plug to 300', put 15 sacks cement on top, drove top plug to 40' and run 10 sacks cement to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lewis Drilling Company
Address 915 Union Center, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Lester Matthew (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Lester Matthew
(Lester Matthew)
915 Union Center, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 30th day of November, 19 56

My commission expires August 20, 1960

R. Derrington
Notary Public.

PLUGGING
SEC 9 T. 27 R. 13 W
PAGE 119 LINE 42

DECEMBER 1956
CONSERVATION DIVISION
Wichita, Kansas


WELL LOG

COMPANY Durbin Bond & Co., Inc., and Lewis Drilling Co. SEC. 9 T. 27S R. 13W
 LOC. NE $\frac{1}{4}$ NE $\frac{1}{4}$ NE $\frac{1}{4}$
 FARM City of Pratt NO. 1

Pratt

COUNTY

KANSAS



TOTAL DEPTH 4571'
 COMM. 11-8-56 COMP. 11-25-56
 SHOT OR TREATED
 CONTRACTOR Lewis Drilling Company
 ISSUED

ELEVATION 1959 K.B.

PRODUCTION

CASING

20	10	
15	\times	8-5/8" - 592'
12	6	
13	5	

FIGURES INDICATE BOTTOM OF FORMATIONS

0	-	55	Clay
55	-	125	Sand
125	-	540	Sand & Shale
540	-	592	Red Bed & Shale
592	-	860	Red Bed
860	-	1115	Red Bed and Shale
1115	-	1675	Red Bed
1675	-	1965	Red Bed & Shale
1965	-	2135	Lime
2135	-	2415	Lime & Shale
2415	-	2500	Lime
2500	-	3670	Lime & Shale
3670	-	3730	Lime
3730	-	3875	Lime & Shale
3875	-	4370	Lime
4370	-	4450	Chert & Lime
4450	-	4463	Chert
4463	-	4505	Shale & Sand
4505	-	4571	Lime & Shale
4571	-		T.D.

GEOLOGIC TOPS:

Heebner	3675'
Douglas	3740'
Brown Lime	3835'
Lansing-Kansas City	3854'
Base/Kansas City	4177'
Checkerboard Limestone	4181'
Base/Checkerboard	4188'
Mississippian	4280'
Kinderhook Chert	4314'
Viola	4344'
Simpson Shale	4436'
Simpson Dolomite	4460'
Simpson Sand	4470'
Arbuckle	4546'

State of KANSAS }
 County of SEDGWICK } SS:

I, Lester Matthew of the Lewis Drilling Company

upon oath state that the above and foregoing is a true and correct copy of the log of the City of Pratt #1 well.

RECEIVED
 STATE CORPORATION COMMISSION

DEC 3 - 1956

Lester Matthew

PLUGGING

SEC. 9 T. 27 R. 13W

PAGE 119 OF 42

Subscribed and sworn to before me this 30th day of November, 1956

My Commission Expires: August 20, 1960

A. R. Derrington
 NOTARY PUBLIC

(A. R. Derrington)