

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Pratt SEC. 11 TWP. 27S RGE. 13 E/W
Location as in quarters or footage from lines:
NW SE NW NE

Locate Well
correctly on above
Section Platt.

Lease Owner Eagle Explorations, Inc.
Lease Name Thomas Well No. 1
Office Address Suite 300, 107 N. Market Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole): Oil
Date Well Completed 2-27-82
Application for plugging filed 1-23-82
Plugging commenced 1-25-83
Plugging completed 1-25-83

Reason for abandonment of well or producing formation
Not Economical To Produce

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Tarbutton-Steve Durant
Producing formation Simpson Depth to top _____ bottom _____ T.D. 4432'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
	Surface			8 5/8"	440'	-0-
	Production			5 1/2"	4432'	2890'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Drilling Fluid from T.D. to 3908'
Set C.I.B.P. @ 3908'

Ran Top Plug As Follows:

- 3 Sacks Hulls
- 20 Sacks Gel
- 100 Sacks Cement
- 20 Sacks Gel
- 1 - 8 5/8" Wooden Plug
- 125 Sacks Cement

Maximum Pump Pressure 600 psig. Shut-In Pressure 400 psig.

Cemented with 50:50 Pozmix + 4% Gel, and 3% CaCl₂

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pratt Well Service

RECEIVED
STATE CORPORATION COMMISSION

MAR 8 1983

CONSERVATION DIVISION
Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.

Carl Durr (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Carl Durr Carl Durr
Suite 300, 107 N. Market Wichita, Ks.
(Address) 67202

SUBSCRIBED AND SWORN TO before me this 4th day of March, 19 83

Sharon J. Clark
Notary Public.

My Commission expires: 3-16-83

