


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD

Pratt County, Sec. 11 Twp. 27S Rge. 13 (E) 13 (W)

Location as "NE/CNW/SW" or footage from lines NE SE NW
Lease Owner Lewis Drilling Company
Lease Name Crow Well No. 1
Office Address 607 Union National Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 1-20 19 55
Application for plugging filed 2-28 19 55
Application for plugging approved 2-28 19 55
Plugging commenced 2-28 19 55
Plugging completed 3-3 19 55
Reason for abandonment of well or producing formation _____



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Marie Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4356 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	403'	None
				5-1/2"	4356'	3167'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

The hole was plugged back to 4324' and casing perforated at 4216'. Filled hole with sand from 4324' to 4200' and ran 5 sacks of cement. Bailed mud to 300', set a 10' rock bridge and ran 20 sacks of cement. Mudded the hole to 40', set a 10' rock bridge and ran 10 sacks of cement on top. Plugging completed.

FILED
CORPORATION COMMISSION
MAR 9 X 1955
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor West Supply Co., Inc.
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
J. Fred Hambright (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. Fred Hambright
607 Union National Bank Bldg., Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 7 day of March 19 55
Arthur P. Derrington Notary Public.
My commission expires August 20, 1956

PLUGGING
FILE SEC 11 T 27 R 13W
BOOK PAGE 100 LINE 14

WELL LOG

COMPANY **Lewis Drilling Company**

SEC. 11 T. 27 R. 13W
LOC. NE 1/4 SE 1/4 NW 1/4

FARM **Crow**

NO. **1**

TOTAL DEPTH **4356'**

COUNTY **Pratt**
KANSAS

COMM. **12-14-54**

COMP. **12-28-54**

SHOT OR TREATED

CONTRACTOR **Lewis Drilling Company**

ISSUED

CASING

20	10				
15	8	5/8"	403'		
12	6				
13	5	1/2"	4356'		

ELEVATION **1939 R.B.**

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

0 -	220	Sand
220 -	575	Red Bed
575 -	725	Shale & Red Bed
725 -	750	Anhydrite
750 -	1770	Sand & Shale
1770 -	1900	Lime
1900 -	2955	Lime & Shale
2955 -	3070	Lime
3070 -	3275	Shale & Lime Brks
3275 -	3345	Lime
3345 -	3510	Lime & Shale
3510 -	3760	Lime
3760 -	3958	Lime & Shale
3958 -	4035	Lime & Shale Stks
4035 -	4310	Lime
4310 -	4356	Lime & Sand
4356		T. D.

Geologic Tops

Brown Lime	3759'
Lansing	3778'
Mississippi	4217'
Simpson Sh.	4303'
Simpson	4356'

PLUGGING

WELL SEC 11 T 27 R 13W

BOOK PAGE 100 LINE 14

WED
 COMMISSION
 MAR 21 1955
 CONSERVATION DIVISION
 Wichita, Kansas

State of Kansas }
 County of Sedgewick } ss:

I, Lo L. Bailey of the Lewis Drilling Company

upon oath state that the above and foregoing is a true and correct copy of the log of the Crow #1 well.

 Subscribed and sworn to before me this 29th day of December, 19 54

My Commission Expires: August 20, 1956

 NOTARY PUBLIC